

PLANILHA DE CÁLCULO DE VOLUME DE ESCAVAÇÃO

CEMITÉRIO

SÃO JORGE DO IVAI-PR

TRECHO		DIAMETRO	EXTENSÃO (m)	MONTANTE	JUSANTE	MÉDIA	ESCAVAÇÃO (m3)	VOLUME TUBO (m3)	ATERRO COM APILOAMENTO	ATERRO SEM APILOAMENTO
CEMITERIO										
PBL1	PBL2	0,40	16,29	1,500	1,500	1,500	24,44	2,95	6,45	15,04
PBL2	PBL3	0,40	20,81	1,500	1,500	1,500	31,22	3,77	8,24	19,22
PBL3	PBL4	0,40	23,71	1,500	1,500	1,500	35,57	4,29	9,38	21,90
PBL4	PBL5	0,40	65,27	1,500	1,500	1,500	97,91	11,81	25,83	60,27
PBL5	PBL6	0,40	63,72	1,500	1,500	1,500	95,58	11,53	25,22	58,84
PBL6	PBL13	0,40	19,50	1,500	2,060	1,780	34,71	3,53	9,35	21,83
PBL7	PBL8	0,40	24,21	1,500	1,500	1,500	36,32	4,38	9,58	22,36
PBL8	PBL9	0,40	17,05	1,500	1,500	1,500	25,58	3,09	6,75	15,74
PBL9	PBL12	0,40	42,30	1,500	1,500	1,500	63,45	7,66	16,74	39,05
PBL10	PBL11	0,40	19,70	1,500	1,500	1,500	29,55	3,57	7,79	18,19
PBL11	PBL12	0,40	16,63	1,500	1,500	1,500	24,95	3,01	6,58	15,36
PBL12	PBL13	0,40	35,92	1,500	1,500	1,500	53,88	6,50	14,21	33,17
PBL13	PBL15	0,60	11,34	2,060	2,450	2,260	35,88	4,62	9,38	21,88
PBL14	PBL15	0,40	8,14	1,500	1,500	1,500	12,21	1,47	3,22	7,52
PBL15	PBL16	0,60	5,14	2,450	2,660	2,560	18,42	2,09	4,90	11,43
PBL16	CXD17	0,60	2,43	2,660	2,770	2,720	9,25	0,99	2,48	5,78
TOTAL			392,16				628,92	75,26	166,10	387,58